BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer
SCHEDULE-B

NAME OF WORK: Improvments to roads and drains at Sampangi ramaiah Layout in Ward -14, Bagalagunte

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	111.60	75.60	Rupees Seventy Five and Sixty Paise Only
2	Removing B.S.Slab of drain and stacking etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	334.80	58.32	Rupees Fifty Eight and Thirty Two Paise Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	83.70	4847.04	Rupees Four Thousand Eight Hundred Forty Seven and Four Paise Only
4	Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	35.65	5228.98	Rupees Five Thousand Two Hundred Twenty Eight and Ninety Eight Paise Only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	334.80	75.60	Rupees Seventy Five and Sixty Paise Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	223.20	639.36	Rupees Six Hundred Thirty Nine and Thirty Six Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP DIVISION
BANGALORE - 560 010

Executive Engineer

	...iding Two line dressing to granite stone slab Complete as ...er specification and direction of Engineer-in-charge of the work.	Sqm	79.20	851.04	Rupees Eight Hundred Fifty One and Four Paise Only
8	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	496.00	993.60	Rupees Nine Hundred Ninety Three and Sixty Paise Only
9	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	558.00	1600.00	Rupees One Thousand Six Hundred Only
10	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	111.60	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP DIVISION
BANGALORE - 560 010

Executive Engineer,
Dasarahalli Division,